




FRONT SIDEWALL

3M BRICK WALL AND ABOVE CLADDING


ANCHOR BOLT PLAN

NOTE: All Base Plates @ 0 (U.N.)



PROJECT	WAREHOUSE	ANCHOR BOLT PLAN		
ID	C163-027	DESIGN: DRS	DRAFT: RBI	CHECK: AAB
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A01		

--



RIGID FRAME: ANCHOR BOLTS & BASE PLATES							
Frm Line	Col Line	Anc. Bolt Qty	Bolt Dia	Base_Plate (mm)		Grout (mm)	
				Width	Length	Thick	
1*	C	8	24	200	706	16	0
1*	A	8	24	200	706	16	0
Moment connection. See table.							
1*	Frame lines:			1	7		

RIGID FRAME: ANCHOR BOLTS & BASE PLATES							
Frm Line	Col Line	Anc. Bolt Qty	Bolt Dia	Base_Plate (mm)		Grout (mm)	
				Width	Length	Thick	
2*	C	8	24	200	706	16	0
2*	A	8	24	200	706	16	0
Moment connection. See table.							
2*	Frame lines:			2	3 4 5 6		

RIGID FRAME: BASIC COLUMN REACTIONS (kN,kN-m)													
Frame Line	Column Line	Dead			Collateral			Live			Wind_Left1		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	1.0	6.3	-3.26	0.3	1.3	-1.13	3.8	14.2	-12.82	-14.1	-18.3	51.05
1*	A	-1.0	6.2	3.27	-0.3	1.3	1.13	-3.8	14.2	12.84	-9.2	-9.4	31.05
Frame Line	Column Line	Wind_Right1			Wind_Left2			Wind_Right2			Wind_Long1		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	9.2	-9.4	-31.06	-17.7	-13.3	56.10	5.6	-4.3	-26.01	5.4	-21.5	-5.82
1*	A	14.1	-18.3	-51.06	-5.6	-4.3	26.00	17.7	-13.3	-56.11	-5.4	-21.5	5.81
Frame Line	Column Line	Wind_Long2			Seismic_Left			Seismic_Right			Seismic_Long1		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	1.8	-16.4	-0.76	-0.3	-0.2	2.05	0.3	0.2	-2.05	0.0	-1.3	0.00
1*	A	-1.8	-16.4	0.76	-0.3	0.2	2.05	0.3	-0.2	-2.05	0.0	-1.3	0.00
Frame Line	Column Line	Seismic_Long2			Temp			LWIND1_L2E			LWIND1_R2E		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	0.0	1.3	0.00	0.1	0.0	-0.89	0.0	-1.9	-0.49	-0.2	-0.2	1.18
1*	A	0.0	1.3	0.00	-0.1	0.0	0.89	0.2	-0.2	-1.18	0.0	-1.9	0.49
Frame Line	Column Line	LWIND2_L2E			LWIND2_R2E								
		Horz	Vert	Mom	Horz	Vert	Mom						
1*	C	0.0	-1.9	-0.49	-0.2	-0.2	1.18						
1*	A	0.2	-0.2	-1.18	0.0	-1.9	0.49						
Frame Line	Column Line	Dead			Collateral			Live			Wind_Left1		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	1.2	9.5	-4.53	0.6	2.3	-2.08	5.3	32.7	-20.00	-17.4	-34.7	73.88
2*	A	-1.2	9.5	4.53	-0.6	2.3	2.08	-5.3	32.7	20.02	-19.5	-14.3	64.94
Frame Line	Column Line	Wind_Right1			Wind_Left2			Wind_Right2			Wind_Long1		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	19.5	-14.3	-64.96	-26.9	-25.4	88.60	10.0	-4.9	-50.23	10.0	-31.9	-10.75
2*	A	17.4	-34.7	-73.89	-10.0	-4.9	50.22	26.9	-25.4	-88.61	-10.0	-31.9	10.73
Frame Line	Column Line	Wind_Long2			Seismic_Left			Seismic_Right			Seismic_Long1		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	3.4	-22.5	-1.43	-0.6	-0.3	3.39	0.6	0.3	-3.39	0.0	-1.3	0.00
2*	A	-3.4	-22.5	1.42	-0.6	0.3	3.39	0.6	-0.3	-3.39	0.0	-1.3	0.00
Frame Line	Column Line	Seismic_Long2			Temp			LWIND1_L2E			LWIND1_R2E		
		Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	0.0	1.3	0.00	0.1	0.0	-0.89	0.0	-3.6	-0.89	-0.4	-0.3	2.15
2*	A	0.0	1.3	0.00	-0.1	0.0	0.89	0.4	-0.3	-2.15	0.0	-3.6	0.89
Frame Line	Column Line	LWIND2_L2E			LWIND2_R2E								
		Horz	Vert	Mom	Horz	Vert	Mom						
2*	C	0.0	-3.6	-0.89	-0.4	-0.3	2.15						
2*	A	0.4	-0.3	-2.15	0.0	-3.6	0.89						
1*	Frame lines:	1	7										
2*	Frame lines:	2	3	4	5	6							

ENDWALL COLUMN: BASIC COLUMN REACTIONS (kN)							
Frm Line	Col Line	Dead	Wind Press	Wind Suct	Seis Long		
		Vert	Horz	Horz	Vert		
1	B	2.0	-18.7	20.7	0.1		
7	B	2.0	-18.7	20.7	0.1		

ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES							
Frm Line	Col Line	Anc. Bolt Qty	Bolt Dia	Base_Plate (mm)		Grout (mm)	
				Width	Length	Thick	
1	B	4	20	200	400	16	0
7	B	4	20	200	400	16	0

NOTES FOR REACTIONS

1. All loading conditions are examined and only maximum/minimum H or V and the corresponding H or V are reported.

2. Positive reactions are as shown in the sketch. Foundation loads are in opposite directions.

3. Bracing reactions are in the plane of the brace with the H pointing away from the braced bay. The vertical reaction is downward.

4. Building reactions are based on the following building data:

Width (mm)= 12200

Length (mm)= 45730

Eave Height (mm)= 9800/ 9800

Roof Slope (rise/100) =10.00/10.00

Roof Dead Load (kN/m2) = 0.10

Wall Dead Load

Left Endwall (kN/m2) = 0.10

Right Endwall (kN/m2) = 0.10

Front Sidewall (kN/m2) = 0.10

Back Sidewall (kN/m2) = 0.10

Live Load (kN/m2) = 0.57

Collateral Load (kN/m2) = 0.05

Wind Speed (m/s) = 39.0

Wind Code = MBMA10

Exposure = B

Closure = Enclosed

Internal Wind Coeff = -0.18, +0.18

Risk Category = -

Importance - Wind = 1.00

Importance - Seismic = 1.00

Seismic Design Category = B

Seismic Coeff (Sms) = 0.16

Temperature Change = 20

5. Loading conditions are:

1 Dead+Collateral+Live

2 Dead+Collateral+0.75Live+0.75Wind_Left1+0.75Floor_Live

3 Dead+Collateral+0.75Live+0.75Wind_Right1+0.75Floor_Live

4 0.6Dead+Wind_Left2

5 0.6Dead+Wind_Right2

6 0.6Dead+Wind_Long1L+LWIND1_L2E

7 0.6Dead+Wind_Long1L+LWIND1_R2E

8 0.6Dead+Wind_Right2+Wind_Suction

9 0.6Dead+Wind_Pressure+Wind_Long2L

10 Dead+Collateral+0.75Snow+0.75Wind_Suction+0.75Wind_Long2L+0.75Slide_Snow

		Reactions in plane of wall		Reactions (kN)		Panel Shear (N/m)		Note
Wall Loc	Col Line	Wind	Seismic	Horz	Vert	Wind	Seis	
L_EW	1							(h)
F_SW	A	1,2	*	7.5	1.6			
		6,7	*	7.5	1.6			
R_EW	7							(h)
B_SW	C	7,6	*	7.5	1.6			
		2,1	*	7.5	1.6			

(h)Rigid frame at endwall

*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.


Reactions for seismic represent shear force, Eh

Reaction values shown are unfactored



PROJECT	WAREHOUSE	ANCHOR BOLT REACTIONS		
ID	C163-027	DESIGN:DRS	DRAFT:RBI	CHECK:ASN
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A03		

FRAME LINES: 1 2 3 4 5 6 7



RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Bolt Dia	Base_Plate (mm)			Grout (mm)	
				Width	Length	Thick		
1*	C	8	20	200	705	16	0	Moment connection. See table.
1*	A	8	20	200	705	16	0	Moment connection. See table.
1*	Frame lines:			1	7			

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Bolt Dia	Base_Plate (mm)			Grout (mm)	
				Width	Length	Thick		
2*	C	8	24	200	706	16	0	Moment connection. See table.
2*	A	8	24	200	706	16	0	Moment connection. See table.
2*	Frame lines:			2	3	4	5	6

RIGID FRAME: BASIC COLUMN REACTIONS (kN,kN-m)

Frame Line	Column Line	---Dead---			---Collateral---			---Live---			---Wind_Left1---		
1*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	1.0	6.1	-3.22	0.3	1.3	-1.12	3.8	14.2	-12.67	-14.0	-18.4	50.72
1*	A	-1.0	6.1	3.23	-0.3	1.3	1.12	-3.8	14.2	12.68	-9.2	-9.3	31.00
Frame Line	Column Line	---Wind_Right1---			---Wind_Left2---			---Wind_Right2---			---Wind_Long1---		
1*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	9.2	-9.4	-31.01	-17.6	-13.3	55.79	5.6	-4.3	-25.94	5.4	-21.5	-5.89
1*	A	14.0	-18.4	-50.73	-5.6	-4.3	25.93	17.6	-13.3	-55.79	-5.4	-21.5	5.88
Frame Line	Column Line	---Wind_Long2---			---Seismic_Left---			---Seismic_Right---			---Seismic_Long1---		
1*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	1.8	-16.4	-0.82	-0.7	-0.4	4.07	0.7	0.4	-4.07	0.0	-1.3	0.00
1*	A	-1.8	-16.4	0.81	-0.7	0.4	4.07	0.7	-0.4	-4.07	0.0	-1.3	0.00
Frame Line	Column Line	---Seismic_Long2---			---Temp---			---F1CRANEA1---			---F1CRANEA2---		
1*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	0.0	1.3	0.00	0.1	0.0	-0.84	-1.4	57.3	23.85	8.0	60.9	-25.98
1*	A	0.0	1.3	0.00	-0.1	0.0	0.84	-8.0	13.1	41.06	1.4	9.5	-8.77
Frame Line	Column Line	---F1CRANEA3---			---F1CRANEA4---			---LWIND1_L2E---			---LWIND1_R2E---		
1*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
1*	C	-1.1	9.8	6.23	8.3	13.4	-43.60	0.0	-1.9	-0.48	-0.2	-0.2	1.15
1*	A	-8.3	60.6	25.28	1.1	57.0	-24.55	0.2	-0.2	-1.15	0.0	-1.9	0.47
Frame Line	Column Line	---LWIND2_L2E---			---LWIND2_R2E---								
1*	C	Horz	Vert	Mom	Horz	Vert	Mom						
1*	C	0.0	-1.9	-0.48	-0.2	-0.2	1.15						
1*	A	0.2	-0.2	-1.15	0.0	-1.9	0.47						
Frame Line	Column Line	---Dead---			---Collateral---			---Live---			---Wind_Left1---		
2*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	1.3	9.6	-4.59	0.6	2.3	-2.11	5.4	32.7	-20.29	-17.5	-34.6	74.45
2*	A	-1.3	9.6	4.60	-0.6	2.3	2.11	-5.4	32.7	20.32	-19.4	-14.4	65.15
Frame Line	Column Line	---Wind_Right1---			---Wind_Left2---			---Wind_Right2---			---Wind_Long1---		
2*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	19.4	-14.4	-65.18	-27.0	-25.3	89.16	9.9	-5.0	-50.47	10.0	-31.9	-10.62
2*	A	17.5	-34.6	-74.46	-9.9	-5.0	50.45	26.9	-25.3	-89.16	-10.0	-31.9	10.60
Frame Line	Column Line	---Wind_Long2---			---Seismic_Left---			---Seismic_Right---			---Seismic_Long1---		
2*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	3.3	-22.5	-1.33	-1.0	-0.6	6.11	1.0	0.6	-6.11	0.0	-1.3	0.00
2*	A	-3.3	-22.5	1.32	-1.0	0.6	6.11	1.0	-0.6	-6.11	0.0	-1.3	0.00
Frame Line	Column Line	---Seismic_Long2---			---Temp---			---F2CRANEA1---			---F2CRANEA2---		
2*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	0.0	1.3	0.00	0.1	0.0	-0.95	-1.1	60.7	23.72	8.3	64.2	-27.00
2*	A	0.0	1.3	0.00	-0.1	0.0	0.95	-8.3	16.1	42.58	1.1	12.6	-8.13
Frame Line	Column Line	---F2CRANEA3---			---F2CRANEA4---			---LWIND1_L2E---			---LWIND1_R2E---		
2*	C	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom	Horz	Vert	Mom
2*	C	-0.8	13.0	5.35	8.6	16.5	-45.36	0.0	-3.6	-0.92	-0.4	-0.3	2.19
2*	A	-8.6	63.8	26.06	0.8	60.4	-24.65	0.4	-0.3	-2.19	0.0	-3.6	0.92
Frame Line	Column Line	---LWIND2_L2E---			---LWIND2_R2E---								
2*	C	Horz	Vert	Mom	Horz	Vert	Mom						
2*	C	0.0	-3.6	-0.92	-0.4	-0.3	2.19						
2*	A	0.4	-0.3	-2.19	0.0	-3.6	0.92						
1*	Frame lines:	1		7									
2*	Frame lines:	2		3	4	5	6						

ENDWALL COLUMN: BASIC COLUMN REACTIONS (kN)

Frm Line	Col Line	Dead Vert	Wind Press Horz	Wind Suct Horz	Seis Long Vert
1	B	2.0	-18.7	20.7	0.1
7	B	2.0	-18.7	20.7	0.1

NOTES FOR REACTIONS

- All loading conditions are examined and only maximum/minimum H or V and the corresponding H or V are reported.
- Positive reactions are as shown in the sketch. Foundation loads are in opposite directions.
- Bracing reactions are in the plane of the brace with the H pointing away from the braced bay. The vertical reaction is downward.
- Building reactions are based on the following building data:

Width (mm)= 12200

Length (mm)= 45730

Eave Height (mm)= 9800/ 9800

Roof Slope (rise/100)= 10.00/10.00

Roof Dead Load (kN/m2)= 0.10

Wall Dead Load

Left Endwall (kN/m2)= 0.10

Right Endwall (kN/m2)= 0.10

Front Sidewall (kN/m2)= 0.10

Back Sidewall (kN/m2)= 0.10

Live Load (kN/m2)= 0.57

Collateral Load (kN/m2)= 0.05

Wind Speed (m/s)= 39.0

Wind Code =MBMA10

Exposure =B

Closure =Enclosed

Internal Wind Coeff =-0.18, +0.18

Risk Category =-

Importance - Wind = 1.00

Importance - Seismic = 1.00

Seismic Design Category =B

Seismic Coeff (Sms)= 0.16

Temperature Change = 20

- Loading conditions are:

1 Dead+Collateral+0.75Live+0.75Wind_Left1+0.75Floor_Live

2 Dead+Collateral+0.75Live+0.75Wind_Right1+0.75Floor_Live

3 0.6Dead+Wind_Left2

4 0.6Dead+Wind_Right2

5 0.6Dead+Wind_Long1L+LWIND1_L2E

6 0.6Dead+Wind_Long1L+LWIND1_R2E

7 Dead+Collateral+F1CRANEA2

8 Dead+Collateral+F1CRANEA3

9 Dead+Wind_Left1/2+F1CRANEA3

10 Dead+Wind_Right1/2+F1CRANEA4

11 Dead+Collateral+F2CRANEA2

12 Dead+Collateral+F2CRANEA3

13 0.6Dead+Wind_Right2+Wind_Suction

14 0.6Dead+Wind_Pressure+Wind_Long2L

15 Dead+Collateral+0.75Snow+0.75Wind_Suction+0.75Wind_Long2L+0.75Slide_Snow

ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Bolt Dia	Base_Plate (mm)			Grout (mm)
				Width	Length	Thick	
1	B	4	20	200	400	16	0
7	B	4	20	200	400	16	0

BUILDING BRACING REACTIONS

---Wall Loc		Col Line	Reactions in plane of wall (kN)		Panel Shear (N/m)	Note
			Wind Horz	Seismic Horz	Wind Seis	
L_EW	1					(h)
F_SW	A	1,2	*	7.5	1.6	
		6,7	*	7.5	1.6	
R_EW	7					(h)
B_SW	C	7,6	*	7.5	1.6	
		2,1	*	7.5	1.6	

(h)Rigid frame at endwall

*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

Reactions for seismic represent shear force, Eh
Reaction values shown are unfactored



PROJECT	WAREHOUSE	ANCHOR BOLT REACTIONS (WITH CRANE)		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	Proposed Warehouse	DATE: 9/JAN/2026		
		C163-027-A03A		



SPLICE PLATES & BOLTS									
Splice Mark	Quan	Top/Bot/Int	Type	Bolt Dia	Len	Plate Size	Wid	Thick	Length
SP1	4	4	0	Gr8.8	20	90	200	16	600
SP2	4	4	0	Gr8.8	20	90	200	16	451

ALTERNATE MEMBER		
Frame Line	OID	Mark
7	A	CL1-4
	B	CL1-1

▽ FLANGE BRACES: FBxx (1 or 2)
 xx=length(mm)
 (1) One Side; (2) Two Sides
 A - L40X40X4

MEMBER TABLE						
Mark	Web Depth	Web	Plate	Outside Flange		
	Start/End	Thick	Length	W x Thk x Length	Inside Flange	
CL1-1	400/ 400		9068	150 x x 9068	150 x x 9068	
RF1-2	351/ 250		5908	125 x x 301	125 x x 5383	
RF1-3	250/ 351		5908	125 x x 6104	125 x x 5383	
CL1-4	400/ 400		9068	125 x x 301	150 x x 9068	

EC-1	W350	125
BRK-1	W350	228



PROJECT	WAREHOUSE	RIGID FRAME ELEVATION		
ID	C163-027	DESIGN:DRS	DRAFT:ASN	CHECK:DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A04		



SPLICE PLATES & BOLTS									
Splice Mark	Quan		Top/Bot/Int	Type	Bolt Dia	Len	Plate Size		
							Wid	Thick	Length
SP1	4	4	0	Gr8.8	20	90	200	16	600
SP2	4	4	0	Gr8.8	20	90	200	16	451

ALTERNATE MEMBER		
Frame Line	OID	Mark
3	A	CL2-1
4	A	CL2-1
5	A	CL2-1
6	B	CL2-3
	A	CL2-1


▽ FLANGE BRACES: FBxx (1 or 2)
 xx=length(mm)
 (1) One Side; (2) Two Sides
 A - L40X40X4

MEMBER TABLE						
Mark	Web Depth		Web Plate		Outside Flange	
	Start/End	Thick	Length	W x Thk x Length	Inside Flange	
CL2-1	400/ 400		9068	150 x 16 x 9068	150 x 16 x 9068	
RF2-2	351/ 250		5908	125 x 16 x 301	125 x 16 x 5383	
CL2-3	400/ 400		9068	125 x 16 x 6104	150 x 16 x 9068	

BRK-1 W350 228



SP1



SP2




PROJECT	WAREHOUSE	RIGID FRAME ELEVATION		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A05		

MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
EB-1	BEAM	3036
EB-2	BEAM	3453
P-1	200Z	8175
P-2	200Z	8280
P-3	200Z	8175
P-4	200Z	6295
E-1	200Z	8175
E-2	200Z	8280
E-3	200Z	8175
E-4	200Z	6300
CB-3	ROD	9220
CB-4	ROD	6130
SP-1	SROD	697
SI-1	SROD	1557
SI-2	SROD	1457
SE-1	SROD	1478
SI-	SROD	1387



PROJECT	WAREHOUSE	ROOF FRAMING		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A06		



ROOF SHEETING PLAN





DENOTE : TURBO VENTILATOR = 012 Qty.




DENOTE : SKY LIGHT 3250 X 1000mm = 012 Qty.




DENOTE: SLOPE DIRECTION

PROJECT	WAREHOUSE	ROOF SHEETING		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A07		



SIDEWALL FRAMING: FRAME LINE A



SIDEWALL FRAMING: FRAME LINE C


BOLT TABLE				
FRAME LINE A & C				
LOCATION	QUAN	TYPE	DIA	LENGTH
Strut	2	Gr8.8	16	70
EB-3 (L)	8	Gr8.8	20	90
EB-3 (R)	4	Gr8.8	16	

SPECIAL BOLTS				
Q ID	QUAN	TYPE	DIA	LENGTH WASH
3	2	Gr8.8	16	70 2


MEMBER TABLE		
FRAME LINE A & C		
MARK	PART	LENGTH
EB-2	BEAM	3453
EB-3	W300	7385
G-7	200Z	8175
G-8	200Z	8280
G-9	200Z	8175
ST-1	T100x	7348
CB-1	ROD	8660
CB-2	ROD	8450
JB-1	SROD	1600
JB-2	SROD	1500
JB-5	SROD	520



PROJECT	WAREHOUSE	SIDEWALL FRAMING		
ID	C163-027	DESIGN:DRS	DRAFT:ASN	CHECK:DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A08		



SIDEWALL SHEETING & TRIM: FRAME LINE A



SIDEWALL SHEETING & TRIM: FRAME LINE C




PROJECT	WAREHOUSE	SIDEWALL FRAMING		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A09		


BOLT TABLE			
FRAME LINE 1 & 7			
LOCATION	QUAN	TYPE	DIA
Columns/Raf	2	Gr8.8	16
			70

MEMBER TABLE		
FRAME LINE 1 & 7		
MARK	PART	LENGTH
EC-1	W350	9583
DJ-1	200C	5980
DH-1	200C	3980
G-1	200Z	6848
G-2	200Z	6265
G-3	200Z	6265
G-4	200Z	6190
G-5	200Z	6265
G-6	200Z	748
JB-1	SR0D	1600
JB-2	SR0D	1500
JB-3	SR0D	170
JB-4	SR0D	1530

FLANGE BRACE TABLE	
FRAME LINE 1 & 7	
VID	MARK
1	FB528
	LENGTH
	528




ENDWALL FRAMING: FRAME LINE 1




ENDWALL FRAMING: FRAME LINE 7



PROJECT	WAREHOUSE	ENDWALL FRAMING		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A10		



ENDWALL SHEETING & TRIM: FRAME LINE 1



ENDWALL SHEETING & TRIM: FRAME LINE 7



PROJECT	WAREHOUSE	ENDWALL FRAMING		
ID	C163-027	DESIGN: DRS	DRAFT: ASN	CHECK: DRS
PROJECT ADDRESS	SASWAD	DATE: 19/JAN/2026		
		C163-027-A11		