










ANCHOR BOLT PLAN
NOTE: All Base Plates © 0 (U.N.)

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	ANCHOR BOLT PLAN		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET 1 OF 1		



Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	ANCHOR BOLT DETAILS		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		

NOTES FOR REACTIONS

1. All loading conditions are examined and only maximum/minimum H or V and the corresponding H or V are reported.
2. Positive reactions are as shown in the sketch. Foundation loads are in opposite directions.
3. Bracing reactions are in the plane of the brace with the H pointing away from the braced bay. The vertical reaction is downward.
4. Building reactions are based on the following building data:

Width

(mm)

= 22596

Length

(mm)

= 20670

Eave Height

(mm)

= 7300 / 7300

Roof Slope

(rise/100)

= 25.00 / 25.00

Roof Dead Load

(kN/m2)

= 0.10

Wall Dead Load

(kN/m2)

= 0.10

Left Endwall

(kN/m2)

= 0.10

Right Endwall

(kN/m2)

= 0.10

Front Sidewall

(kN/m2)

= 0.10

Back Sidewall

(kN/m2)

= 0.10

Live Load

(kN/m2)

= 0.57

Collateral Load

(kN/m2)

= 0.05

Wind Speed

(m/s)

= 36.1

Wind Code

= MBMA10

Exposure

= B

Closure

= Enclosed

Internal Wind Coeff

= -0.18, +0.18

Risk Category

= -

Importance - Wind

= 1.00

Importance - Seismic

= 1.00

Seismic Design Category

= B

Seismic Coeff

(Sms)

= 0.33

Temperature Change

= 20

5. Loading conditions are:

1 Dead+Collateral+Live

2 Dead+Collateral+0.75Live+0.75Wind_Long2R+0.75Floor_Live+0.75LWIND2_L2E

3 Dead+Collateral+0.75Live+0.75Wind_Long2R+0.75Floor_Live+0.75LWIND2_R2E

4 0.6Dead+Wind_Left1

5 0.6Dead+Wind_Right1

6 0.6Dead+Wind_Left2

7 0.6Dead+Wind_Right2


8 0.6Dead+Wind_Long1L+LWIND1_L2E

9 0.6Dead+Wind_Long1L+LWIND1_R2E

10 1.02Dead+1.02Collateral+0.52Seismic_Right+0.75Floor_Live

11 0.6Dead+Wind_Right2+Wind_Suction

12 0.6Dead+Wind_Pressure+Wind_Long2L



RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc._Bolt Qty	Dia	Base_Plate (mm)			Grout (mm)
				Width	Length	Thick	
1*	D	4	20	200	300	16	500
1*	A	4	20	200	300	16	500

1* Frame lines: 1 5

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc._Bolt Qty	Dia	Base_Plate (mm)			Grout (mm)
				Width	Length	Thick	
2*	D	4	20	200	300	16	500
2*	A	4	20	200	300	16	500

2* Frame lines: 2 3 4

RIGID FRAME: BASIC COLUMN REACTIONS (kN)

Frame Line	Column Line	----Dead----		--Collateral--		----Live----		--Wind_Left1--		--Wind_Right1--		--Wind_Left2--	
		Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
1*	D	3.0	8.0	0.8	1.7	9.0	18.3	-13.1	-18.9	-0.4	-12.2	-12.8	-13.5
1*	A	-3.0	8.0	-0.8	1.7	-9.0	18.3	0.4	-12.2	13.1	-18.9	0.1	-6.7

Frame Line	Column Line	--Wind_Right2--		--Wind_Long1--		--Wind_Long2--		--Seismic_Left		Seismic_Right		Seismic_Long1	
		Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
1*	D	-0.1	-6.7	-3.0	-27.8	-2.3	-22.3	-0.9	-0.5	0.9	0.5	0.0	-2.0
1*	A	12.8	-13.5	3.0	-27.8	2.3	-22.3	-0.8	0.5	0.8	-0.5	0.0	-2.0

Frame Line	Column Line	Seismic_Long2		LWIND1_L2E--		LWIND1_R2E--		LWIND2_L2E--		LWIND2_R2E--	
		Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
1*	D	0.0	2.0	0.1	-1.7	-0.4	-0.3	0.1	-1.7	-0.4	-0.3
1*	A	0.0	2.0	0.4	-0.3	-0.1	-1.7	0.4	-0.3	-0.1	-1.7

Frame Line	Column Line	----Dead----		--Collateral--		----Live----		--Wind_Left1--		--Wind_Right1--		--Wind_Left2--	
		Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
2*	D	4.2	10.5	1.4	2.9	15.8	32.2	-18.6	-24.8	3.9	-15.0	-19.9	-15.1
2*	A	-4.2	10.5	-1.4	2.9	-15.8	32.2	-3.9	-15.0	18.6	-24.8	-2.7	-5.4

Frame Line	Column Line	--Wind_Right2--		--Wind_Long1--		--Wind_Long2--		--Seismic_Left		Seismic_Right		Seismic_Long1	
		Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
2*	D	2.7	-5.4	-5.3	-37.9	-4.0	-28.2	-1.0	-0.6	1.0	0.6	0.0	-2.0
2*	A	19.9	-15.1	5.3	-37.9	4.0	-28.2	-1.0	0.6	1.0	-0.6	0.0	-2.0

Frame Line	Column Line	Seismic_Long2		LWIND1_L2E--		LWIND1_R2E--		LWIND2_L2E--		LWIND2_R2E--	
		Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert	Horz	Vert
2*	D	0.0	2.0	0.1	-3.0	-0.8	-0.6	0.1	-3.0	-0.8	-0.6
2*	A	0.0	2.0	0.8	-0.6	-0.1	-3.0	0.8	-0.6	-0.1	-3.0

1* Frame lines: 1 5

2* Frame lines: 2 3 4

ENDWALL COLUMN: BASIC COLUMN REACTIONS (kN)

Frm Line	Col Line	Dead Vert	Wind Press Horz	Wind Suct Horz	Seis Long Vert
1	C	1.4	-15.2	15.8	0.1
1	B	1.4	-15.2	15.8	0.1
5	B	1.4	-15.2	15.8	0.1
5	C	1.4	-15.2	15.8	0.1

ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc._Bolt Qty	Dia	Base_Plate (mm)			Grout (mm)
				Width	Length	Thick	
1	C	4	20	200	300	16	500
1	B	4	20	200	300	16	500
5	B	4	20	200	300	16	500
5	C	4	20	200	300	16	500

BUILDING BRACING REACTIONS

---Wall Loc	---Col Line	Reactions in plane of wall (kN)				of wall Panel_Shear (N/m)		Note
		Wind	Seismic	Wind	Seis	Wind	Seis	
L_EW	1							(h)
F_SW	A	1,2	*	11.8	2.3			
		4,5	*	11.8	2.3			
R_EW	5							(h)
B_SW	D	5,4	*	11.8	2.3			
		2,1	*	11.8	2.3			

(h)Rigid frame at endwall

*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

Reactions for seismic represent shear force, Eh
Reaction values shown are unfactored

Sivoko Steel Structures Ltd.


PROJECT	Proposed Warehouse	ANCHOR BOLT REACTIONS		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025\$ SHEET 1 OF 1		

BOLT TABLE			
FRAME LINE 1			
LOCATION	QUAN	TYPE	DIA LENGTH
Columns/Raf	2	Gr8.8	16 70

MEMBER TABLE		
FRAME LINE 1		
MARK	PART	LENGTH
EC-1	W25a125	7692
EC-2	W25a125	7692
G-1	200Z15	6500
G-2	200Z15	4685
G-3	200Z15	10676
G-4	200Z15	8947
G-5	200Z15	6500
G-6	200Z15	4685
JB-1	SR0D12	1520
JB-2	SR0D12	1300
JB-3	SR0D12	1200

FLANGE BRACE TABLE		
FRAME LINE 1		
VID	MARK	LENGTH
1	FB424	424

CONNECTION PLATES		
FRAME LINE 1		
ID	MARK/PART	
1	d1	
2	r1	



ENDWALL FRAMING: FRAME LINE 1


Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	ENDWALL FRAMING		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		

BOLT TABLE				
FRAME LINE 5				
LOCATION		QUAN	TYPE	DIA
Columns/Raf		2	Gr8.8	16
				70

MEMBER TABLE		
FRAME LINE 5		
MARK	PART	LENGTH
EC-1	W25a125	7692
EC-2	W25a125	7692
G-1	200Z15	6500
G-2	200Z15	4685
G-3	200Z15	10676
G-4	200Z15	8947
G-5	200Z15	6500
G-6	200Z15	4685
JB-1	SROD12	1520
JB-2	SROD12	1300
JB-3	SROD12	1200

FLANGE BRACE TABLE		
FRAME LINE 5		
VID	MARK	LENGTH
1	FB424	424

CONNECTION PLATES		
FRAME LINE 5		
ID	MARK/PART	
1	d1	
2	r1	





ENDWALL FRAMING: FRAME LINE 5

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	ENDWALL FRAMING		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		

SPlice PLATES & BOLTS								
Splice Mark	Quan		Bolt		Plate Size			
	Top/Bot	Int	Type	Dia	Len	Wid	Thick	Length
SP1	4	4	Ør8.8		20	90	200	16
SP2	4	4	Ør8.8		20	90	200	16
SP3	4	4	Ør8.8		20	90	200	16

▽FLANGE BRACES: FBxx (1 or 2)
xx=length(mm)
(1) One Side; (2) Two Sides
A - L40X40X4

MEMBER TABLE					
Mark	Web Depth		Web Plate		Outside Flange W x Thk x Length
	Start/End	Thick	Length		
CL1-1	250/ 700	5	6225		150 x 5 x 6225
RF1-2	551/ 351	4	5475		125 x 5 x 366
RF1-3	350/ 450	4	6000		125 x 5 x 5586
					125 x 5 x 6000




RIGID FRAME ELEVATION: FRAME LINE 1 5

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	RIGID FRAME ELEVATION		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		

SPLICE PLATES & BOLTS								
Splice Mark	Quan		Bolt			Plate Size		
	Top/Bot	Int	Type	Dia	Len	Wid	Thick	Length
SP1	4	4	Ør8.8		20	90	200	16
SP2	4	4	Ør8.8		20	90	200	16
SP3	4	4	Ør8.8		20	90	200	16

▽FLANGE BRACES: FBxx (1 or 2)
xx=length(mm)
(1) One Side; (2) Two Sides
A - L40X40X4

MEMBER TABLE						
Mark	Web Depth		Web Plate		Outside Flange	
	Start/End	Thick	Length		W x Thk x Length	Inside Flange W x Thk x Length
CL2-1	250 / 700	5	6225		150 x 5 x 6225	150 x 8 x 6241
RF2-2	356 / 551	5	781		125 x 5 x 366	125 x 8 x 4698
RF2-3	551 / 351	4	4694		125 x 5 x 5586	
	350 / 450	4	6000		125 x 5 x 6000	125 x 5 x 5887



Bolt Dia= 20
Plate Thk= 16


Bolt Dia= 20
Plate Thk= 16

Bolt Dia= 20
Plate Thk= 16

Bolt Dia= 20
Plate Thk= 16

RIGID FRAME ELEVATION: FRAME LINE 2 3 4


Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	RIGID FRAME ELEVATION		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		



ROOF FRAMING PLAN

MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
P-1	200Z15	5705
P-2	200Z15	5750
P-3	200Z15	5705
E-1	200Z15	5705
E-2	200Z15	5750
E-3	200Z15	5705
CB-3	ROD20	7810
CB-4	ROD20	6900
SP-1	SROD12	682
SI-1	SROD12	1721
SE-1	SROD12	1641

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	ROOF FRAMING		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		




COLUMNS & RAFTERS MARKING PLAN

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	ROOF FRAMING		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025	SHEET	OF

BOLT TABLE				
FRAME LINE D				
LOCATION	QUAN	TYPE	DIA	LENGTH
Strut	2	Gr8.8	16	70

SPECIAL BOLTS					
Ø ID	QUAN	TYPE	DIA	LENGTH	WASH
3	2	Gr8.8	16	70	2

MEMBER TABLE		
FRAME LINE D		
MARK	PART	LENGTH
G-7	200Z15	5705
G-8	200Z15	5750
G-9	200Z15	5705
ST-1	T72x32	4958
CB-1	ROD20	6680
CB-2	ROD20	5190
JB-1	SROD12	1520
JB-2	SROD12	1300
JB-4	SROD12	700




SIDEWALL FRAMING: FRAME LINE D

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	SIDEWALL FRAMING		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET OF		

BOLT TABLE				
FRAME LINE A				
LOCATION	QUAN	TYPE	DIA	LENGTH
Strut	2	Gr8.8	16	70

SPECIAL BOLTS					
Ø ID	QUAN	TYPE	DIA	LENGTH	WASH
3	2	Gr8.8	16	70	2

MEMBER TABLE		
FRAME LINE A		
MARK	PART	LENGTH
G-7	200Z15	5705
G-8	200Z15	5750
G-9	200Z15	5705
ST-1	T72x32	4958
CB-1	ROD20	6680
CB-2	ROD20	5190
JB-1	SROD12	1520
JB-2	SROD12	1300
JB-4	SROD12	700



SIDEWALL FRAMING: FRAME LINE A

Sivoko Steel Structures Ltd.				
PROJECT	Proposed Warehouse	SIDEWALL FRAMING		
ID	Q-1467	DESIGN:	DRAFT:	CHECK:
PROJECT ADDRESS	Proposed Warehouse	DATE: 15/DEC/2025 SHEET 1 OF 1		